BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No EE/YNK-D/E-PMT/07/2018-19 Dated: 16-02-2019

APPROVED TENDER SCHEDULE –'B'

Item-08

Name of Work:-Providing UGD Work System in ward no:02 of Yelahanka Sub Division

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri R Ranganath	
				Rate	Rate In Words
1	KSRB 2-2 : Earthwork excavation by manual means for foundation of buildings, water supply and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications. – do – in ordinary soil. No. KBS 2.1(a) / 2.3.5 (P.No-6 ,I No-2.3 of PW,P&IWTD S.R 2018-19)	Per Cum	704.70	357.03	Rupees Three Hundred Fifty Seven and Paise Three Only
2	KSRB 2-2.3 : Excavation by manual means for foundation of buildings, water supply & sanitary lines and electrical conduits etc., either in pits or in trenches 1.50m and above in width, in soft rock / ordinary rock not exceeding 1.50mtrs in depth including stacking the excavated stuff clear from edges of excavation with lead upto 50mt including cost of explosives, labour, HOM complete as per specifications. specification. No. KBS 2.1C/2.9.4/2.18/2.19 (P.No.06, I.No.2.5 of PW,P&IWTD S.R 2018-19)	Per Cum	417.60	819.15	Rupees Eight Hundred Nineteen and Paise Fifteen Only
3	KSRB 12-1.4 : Providing and laying in position to required level or slope internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, testing of pipes and joints,including cost of materials, labour charges complete as per specifications. Specification No. KBS 12.2.5 / 12.7 - do- 230mm (Page no.70, item no.11.4 of KPWD S.R 2018-19).	Per Mtr	870.00	640.03	Rupees Six Hundred Forty and Paise Three Only
4	KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications. (P.No.7, I.No. 2.11 of KPWD S.R18-19)	Per Cum	934.20	144.48	Rupees One Hundred Forty Four and Paise Forty Eight Only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri R Ranganath	
				Rate	Rate In Words
5	KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406 (P.No.155, I.No.20.18 of KPWD S.R 2018-19).	Per Cum	155.70	2254.44	Rupees Two Thousand Two Hundred Fifty Four and Paise Forty Four Only
6	KSRB 12-5.5 : Constructing brick masonry circular type manhole 1.52 m internal dia at bottom,and 0.56m dia at top, with table moulded and non-modular bricks of class designation 50 in cement mortar 1:4, inside cement plaster 12mm thick with cement mortar 1:3, finished with a floating coat of neat cement, foundation concrete M 10 mixed using 40mm and down size granite metal and making necessary channel in cement concrete 1:2:4 mix with 20mm anddown size granite metal, finished with a floating coat of neat cement, with S.F.R.C. cover and frame (heavy duty, HD-20 grade designation) 560mm internal diameter confirming to IS :12592, total weight length of cover and frame to be not less than 182 kg, fixed in cement concrete M 15 20mm and down size broken granite metal, providing and removing centering, shuttering including cost of materials, labour charges, HOM of mechineries complete as per specifications. (Excavation, footrests and 12mm thick cement plaster on the external surface shall be paid seperately) Specification No. KBS 12.4 -do- 2.30m deep (Page no.72, item no.11.41 of KPWD S.R 2018-19).	Per Nos	30.00	54782.46	Rupees Fifty Four Thousand Seven Hundred Eighty Two and Paise Forty Six Only
7	KSRB 12-6.1 : Providing 20mm square M.S footrest and fixing in manhole with M 10 cement concrete block of 20x20x10cms, using 20mm and down size metal of size including cost of materials, labour charges, curing complete as per specifications. Specification No. KBS 12.4.6.(P.No.73, I.No.11.44 of KPWD S.R 2016-17).	Per Nos	80.00	329.57	Rupees Three Hundred Twenty Nine and Paise Fifty Seven Only
8	KSRB15-3.3 : Providing 12mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(P.No.115, I.No.15.11 of KPWD S.R 2018-19).	Per Sqm	101.38	230.46	Rupees Two Hundred Thirty and Paise Forty Six Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri R Ranganath	
				Rate	Rate In Words
9	KSRB 2.6 : Providing and filling sand in foundation to required depth for sub soil treatment including watering ramming with all lead and lift complete as per specifications. specification. No. KBS 2.10.2 (P.No.7, I.No.2.13 of KPWD S.R 2018-19).	Per Cum	155.70	2459.83	Rupees Two Thousand Four Hundred Fifty Nine and Paise Eighty Three Only
10	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH -100/ Chapter 1 From 0 to 5	Per cmtr	694.70	78.63	Rupees Seventy Eight and Paise Sixty Three Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.